



# COOPER STREET Dalby



**ERGON ENERGY  
DALBY DEPOT UPGRADE**



DRAWING LIST		
NO.	DESCRIPTION	DATE
001	GENERAL NOTES	15/01/15
002	PROPOSED WORKS	15/01/15
003	PROPOSED WORKS	15/01/15
004	PROPOSED WORKS	15/01/15
005	PROPOSED WORKS	15/01/15
006	PROPOSED WORKS	15/01/15
007	PROPOSED WORKS	15/01/15
008	PROPOSED WORKS	15/01/15
009	PROPOSED WORKS	15/01/15
010	PROPOSED WORKS	15/01/15
011	PROPOSED WORKS	15/01/15
012	PROPOSED WORKS	15/01/15
013	PROPOSED WORKS	15/01/15
014	PROPOSED WORKS	15/01/15
015	PROPOSED WORKS	15/01/15
016	PROPOSED WORKS	15/01/15
017	PROPOSED WORKS	15/01/15
018	PROPOSED WORKS	15/01/15
019	PROPOSED WORKS	15/01/15
020	PROPOSED WORKS	15/01/15



**DEVELOPMENT SUMMARY**  
 LOCATION: DALBY  
 LOCALITY: DALBY  
 TOTAL AREA: 2.148  
 NO. OF LOTS: 1

**NAME OF AUTHORITY**  
 HERBERTSWAIN REGIONAL COUNCIL

**PROPERTY DESCRIPTION**  
 LOT 101 (101/102)  
 PARCEL OF DALBY  
 COUNTY OF HERBERTSWAIN

**SURVEY ORIGIN**  
 PLAN NO: 2011/001  
 DATE: 15/01/15  
 SURVEYOR: MAREE NORTH SURVEYS PTY LTD



## Project Data Sheet

Client:  
Ergon Energy

Project Location:  
Cooper Street, Dalby

Contract Value:  
\$900,000

Year completed:  
2015

Scope:  
Earthworks  
Drainage  
Electrical  
Sprayed bituminous and asphaltic surfacing  
Kerb and channel  
Signage

### ALL ENQUIRIES

Phone: +61 7 3807 9346  
[admin@civcorp.com.au](mailto:admin@civcorp.com.au)  
[civcorp.net.au](http://civcorp.net.au)

3 Production Street  
Beenleigh Qld 4207

Over the years Civcorp has had a long and prosperous working relationship with Ergon Energy having delivered projects all across Queensland in locations such as Biloela, Mundubbera, Stanthorpe and Mackay.

Civcorp continued this relationship delivering an upgrade to the Ergon Energy Depot in Dalby.

The works were designed by BMD Urban and included new concrete pavements and drainage around the depot, an upgrade to the outdoor asphalt surfacing, new timber pole storage racks, cement treated pavements, additional car parking facilities, upgraded entrances and exits, kerbing, signage along with custom made fencing and electronically controlled cantilever gates.

BMD Urban supervised the works and acted as the Client's Representative overseeing all Quality Assurance functions and construction query resolution.

Overall the works were completed on time and under budget with no disruption to Ergon Energy's use of the depot.

Through our engagement with local suppliers and business Civcorp was also able to add value to the design through obtaining local knowledge on construction methodologies, researching the experiences of the local community with certain aspects of the design and passing these back to BMD Urban as construction innovations.

One such example of this was Civcorp's suggestion to amend the cement treated base design based on advice from the local government on their experience with the product. We suggested an alternative that incorporated a high strength woven geotextile which was accepted by BMD Urban and Ergon Energy and ultimately avoided issues experienced by other people in the area associated with Black soil.

This is but one example of Civcorp's dedication to client satisfaction and innovation through construction.

