



AAT Resurfacing – Stage 1 Australian Amalgamated Terminals



Australian Amalgamated Terminals operates a large vehicle import/export terminal at the Port of Brisbane. The site required resurfacing, new linemarking, as well as stormwater and service pit upgrades.

Civcorp commenced works by replacing all pit lids and grates and ensuring site was ready for profiling. Profiling was completed on over 16,000m² of existing asphalt and profiled product sent for recycling.

Various asphaltic products were used depending on the planned use of the area. AC20H and AC14H products were used extensively as well as custom Portmix product. In total nearly 2200 tonnes were laid. Civcorp also liaised closely with AAT to ensure line marking was completed as per client expectations and optimised available space.

Civcorp completed these works ensuring minimal disruption to port traffic including imported vehicle unloading and large container handlers and forklifts.



Project Data Sheet

Client:

PPQ for Australian Amalgamated Terminals and Port of Brisbane

Project Location:

Port of Brisbane

Contract Value:

\$1,100,000

Year completed:

2019

Scope:

Service Relocation
Stormwater Grate Install
Profiling
Asphalt
Concrete
Linemarking
Complex Traffic Control

ALL ENQUIRIES

Phone: +61 7 3807 9346

admin@civcorp.com.au

civcorp.com.au

3 Production Street
Beenleigh Qld 4207